



#

Shelby County Schools

Department of Major Construction

June 17, 2021

To: Ben Townsend, Farm to School Program Manager
Department of Nutrition Services

From: Anthony Wright, Construction Manager
Department of Major Construction

Re: Kingsbury HS NW Courtyard Drainage

The Scope of Work for the Drainage Bid Solicitation should be as follows:

1. Call 811 Before You Dig
2. Existing gutter downspouts leveled at finished floor with concrete downspout splash blocks
3. Cut and/or fill as needed to grade 2" below finish floor at perimeter
4. Slope to center and existing catch basins (exception to be existing equipment pads for A/C condensers). Remove dirt offsite, if necessary
5. Prepare soil and sod with Zoysa
Add Alternate: seed finished site with local grass mix